

Section 07 21 29
K-13® Parking Garage Insulation With Cleanable Overcoat
Specification Guide 6/16

PART 1 – GENERAL

1.01 Section Includes

- A. Sprayed cellulose thermal insulation.

1.02 Related Items

- A. Clips, hangers, supports, sleeves and other attachments to spray bases are to be placed by other trades prior to the application of sprayed insulation.
- B. Ducts, piping, conduit or other suspended equipment shall not be positioned until after the application of sprayed insulation.
- C. Roof penetrations to be installed prior to application.

1.03 Quality Assurance

- A. Manufacturer must have a current Underwriters Laboratories (UL) Code Evaluation Report.
- B. Manufacturer must be in compliance with the 2009 and 2012 International Building Code.
- C. Manufacturer must be ISO 9001:2008 Certified.
- D. Applicator: Licensed by manufacturer.
- E. Manufacturer must subscribe to independent laboratory follow-up inspection services of Underwriters Laboratories and Factory Mutual. Each bag shall be labeled accordingly.
- F. Mock-up: Apply a 100 square foot representative sample to be reviewed by the Architect and/or Owner prior to proceeding.

1.04 Submittals

- A. Submit product data that the product meets or exceeds the following specified requirements.
 - 1. Bond strength shall be greater than 100 psf per ASTM E 736.
 - 2. Product shall be Class 1 Class A per ASTM E 84/ UL 723.
 - 3. Non-corrosive per ASTM C 739.
 - 4. Bond Deflection per ASTM E 759: 6" Deflection in 10' Span – No Spalling or Delamination.
 - 5. R-Value to be 3.75 per inch per ASTM C518.
 - 6. Comply with IBC 803.3/2009 IBC 803.10 stability requirements for interior finishes.
 - 7. Meet ASTM C 1149
- B. Manufacturer's written certification that product contains no asbestos, fiberglass or other man-made mineral fibers.
- C. Copy of manufacturer's ISO 9001:2008 Certification.
- D. Minimum Fiber Recycled Content to be 75%.
- E. Cannot contain any added Urea-Formaldehyde Resins.

1.06 Delivery, Storage and Handling

- A. Deliver in original, unopened containers bearing name of manufacturer, product identification and reference to U.L. testing.
 - B. Store materials dry, off ground, and under cover.
 - C. Protect liquid adhesive from freezing.
 - D. Water to be potable.
-
-

Section 07 21 29
K-13® Parking Garage Insulation With Cleanable Overcoat
Specification Guide 6/16

PART 2 – PRODUCTS

2.01 Acceptable Manufacturers

- A. International Cellulose Corporation
12315 Robin Boulevard
Houston, Texas 77045
(713) 433-6701 or (800) 444-1252
FAX: (713) 433-2029
www.spray-on.com
icc@spray-on.com
- B. For approved applicators contact ICC at 800-444-1252.

2.02 Materials

- A. K-13 Spray-On-Systems.
 - 1. Color shall be Light Gray.
 - 2. Application to be top-coated with Protek-13 protective coating.
 - 3. Comply with local Building Code requirements.
 - 4. Material to have been tested in accordance with ASTM E 1042. Testing laboratory must be NVLAP accredited.

PART 3 – EXECUTION

3.01 Examination

- A. Examine surfaces and report unsatisfactory conditions in writing. Do not proceed until unsatisfactory conditions are corrected.
- B. Verify surfaces to receive spray insulation to determine if priming/sealing is required to insure bonding and/or to prevent discoloration caused by migratory stains.

3.02 Preparation

- A. Provide masking, drop cloths or other satisfactory coverings for materials/surfaces that are not to receive insulation to protect from over-spray.
 - B. Coordinate installation of the sprayed cellulose fiber with work of other trades.
 - C. Prime surfaces as required by manufacturer's instructions or as determined by examination.
-
-

Section 07 21 29
K-13® Parking Garage Insulation With Cleanable Overcoat
Specification Guide 6/16

3.03 Installation

- A. Install spray applied insulation according to manufacturer's recommendations.
- B. Install spray applied insulation to achieve an average R-Value of ____.
- C. Cure insulation with continuous natural or mechanical ventilation.
- D. Remove and dispose of over-spray.

3.04 Protection

- A. Protect finished installation under provision of Division 1.

END OF SECTION
